REPLY TO PRE-BID QUERIES FOR Estimate for the Work of Providing and Laying 1600mm dia RCC NP-3 pipe line from Outer Ring Road near Hennur Police Station to Rajacanal STP

Tender BWSSB/ CE(WWM-WEST)/ACE(WWM-N-W)/DCE(WWM-E&W)/TA-2/841/2023-24 Dt : 01.02.2024
BWSSB/2023-24 /WS/Work_INDENT312

Sl. No	Document Name	Page No/Section Name	Statement	Query	Submitted on	Reply
1.	Bill of Quantities	BOQ No 42 43 44	For Manufacture of RCC NP3 Class Pipes by using OPC	Whereas it is mentioned as SRC and marked with ISI in Chapter 10 of Section 7 Clause 2 1 1 on Page 59 please clarify	07-02-2024 15:35:57	Tender condition prevails.
2	Cement content	Table 4 on Page 69 Section 7 Technical Specification	Cement content of concrete is not mentioned	Please clarify	07-02-2024 15:37:43	As per IS Standards.
3	Contract Data	Section 6	There is no Mobilisation Advance	10 Percent Interest Free Mobilization Advance can be considered	07-02-2024 15:24:35	The amounts of the advance payment are: [42] Nature of Advance / Amount (Rs.) / Conditions to be fulfilled 1. Mobilization / 05% of the Contract price / On submission of un-conditional Bank Guarantee. (to be drawn before end of 45 days) Repayment of advance payment for mobilization : [42] The advance loan shall be repaid with percentage deductions from the interim payments certified by

CamScanner

						the Engineer under the Contract. Deductions shall commence in the 3rd Interim Payment Certificate following that in which the total of all such payments to the Contractor has reached not less than 15 percent of the Contract Price or 3 months from the date of payment. The first installment of advance has to be recovered within 10 installments, whichever period concludes earlier, and shall be made at the rate of 7.5 percent of the amounts of all Interim Payment Certificates until such time as the loan has been repaid, always provided that the loan shall be completely repaid prior to the expiry of the original time for completion pursuant to Clauses 17 and 26
4	For Relaxation in Tender conditions	Tender document page no 4 to 9	Eligibilty criteria have been relaxed for the tenders called by WWM EAST as referenced in indent No BWSSB/2022-23/WS/WORK INDENT/7362 It is clearly stated that the eligibility criteria for 900 mm Dia Rcc pipelines or larger will be the same as those for the 900 mm Dia Rcc pipe line	Requesting for relaxation in the eligibility criteria as 467 Rmt of 900mm Dia RCC Np3 class sewers/16 rmt of 1200 mm dia casing pipe trenchless and 1591cum of RCC M20 grade in lieu of 467 rmt of 1800mm and above The Related documents and query letter have been submitted to your office by hand for further consideration	05-02-2024 01:54:56	Tender condition prevails.
5	Hard Rock	Page 45 Clause 12	The Hard Rock obtained during execution will not be auctioned by the Board	However Rupees 70 per Cubic Meter Plus applicable GST of HR will be recovered from	07-02-2024 15:47:44	Tender condition prevails.

CamScanner

			because of the restriction in stocking of HR in site and safety issues	the firm in running bills Please clarify		
6	Hard Rock	Page 66 Section 7	In case of Hard Rock requiring chipping or chiseling measurement shall be taken prior to and after chiseling and the volume of rock excavation shall be measured based on this difference In case of excavation HR by blasting the quantity of rock excavated shall be stacked along the side of trench which will be cross checked with a trench dimensions The excavation in rock shall be paid on stock measurements with a deduction of 40 Percent in volume for voids	However the payment for rock excavation by blasting shall be limited so as not to exceed the volume computed based on the trench dimensions as per specifications in Item No 12 3 on Page 66 Please clarify	07-02-2024 15:54:41	Trench measurements will be considered.
7	Payment	Section 6	There is no payment terms	Payment terms can be considered as After Supply of RCC Pipes 75 Percent After laying and jointing 20 Percent After conducting flow test and commissioning 5 Percent	07-02-2024 15:26:10	**Payment Terms.** The employer will make the payment to the items of pipelines on the following terms-(Clause 43 GCC). 70% of the contract price — After supply of DWC/RCC pipes to site of work 25% of the contract price — After laying of pipes.

CamScanner

						05% of the contract price	After Completion and commissioning of Pipeline work including complete restoration.
8	Site Office	Engineers Requirement	Requirement of Site Office including furniture survey instruments and personal computer and Laptop with accessories Printers	The same has not been considered in BOQ The cost for the same to be considered during tender evaluation or delete from the contract	07-02-2024 15:40:05	Tender condition prevails.	
9	Transport	Page 50 Clause 27 5	Requirement of Transport vehicle New top end Four Plus One seated AC Maruti grand Vitara Alpha Plus intelligent fully loaded	For providing vehicle we would like to inform you that recently in Arkavathy Tender the same was included by incorporating to provide vehicle and the capital cost of vehicle will be reimbursed at actual cost under provisional sum excluding insurance The same has not been considered either you consider the same or delete from the contract	07-02-2024 15:45:33	Tender condition prevails.	

Chief Engineer(WWM-W)
BWSSB